

It shall apply from: 07-06-2019 r.

THE ASSEMBLY INSTRUCTION OF: SKATEPRAK SET No. 21 PRODUCT CODE: 102170



ASSEMBLY INSTRUCTION

Product code: 102170 Skatepark set no. 21




TABLE OF CONTENTS

INTROI	DUCTION	2
	1 – Preparatory work – safety zone	
	2 – Assembly of the construction	
	List of components	
	Assembly scheme	

INTRODUCTION

• Overall dimensions: 6,16 x 3,87 x 0,70 m




Product code: 102170 Skatepark set no. 21



STAGE 1 - Preparatory work - safety zone

- Secure the assembly site to keep others at a distance
- Set the construction in a designated place having regard to required impact area.



WARNING!

Installation shall be performed in accordance with safety & health standards




STAGE 2 - Assembly of the construction

1. List of components

No	Name of component	Dimensions	Qty.	Norm
1	Box 700 2S	1200x1200x700	2	
2	Box 700 3S	1200x1200x700	2	
3	Bank 700		4	
4	Ramp 700		2	
5	Stainless steel toe plate for Bank	250x1200	4	SN.250.000
6	Stainless steel toe plate for Ramp	350x1200	2	SN.350.000
7	Sheet metal connector of Box and Box	100x1200x5	2	SP.Ł.100
8	Sheet metal connector of Bank and Box	139x1200x5	4	SP.Ł.101
9	Sheet metal connecting Ramp and Box 700	1 200x145x5	2	SP.Ł.105 LR
10	Side rail for Bank 700		4	SP.BK.002
11	Side rail for Ramp 700		2	SP.RP.005
12	Side rail for Box		1	SP.BX.004 L
13	Side rail for Box		1	SP.BX.004 R
14	Countersunk screw - Torx	TX45 – M8x16	36	ISO 14581
15	Countersunk screw	M10 x 20	92	DIN 7991
16	Countersunk screw	M10 x 25	52	DIN 933
17	Washer	Ø30xØ10,5x2,5	52	DIN 9021
		(M10)		
18	Plastic expansion bolt	Ø10x80	12	


2. Assembly scheme

Screw the steel toe plates (point 5) to the Banks (point 3) by using screws and washers of point 14, 16 and 17.







Screw the steel toe plates (point 6) to the Ramps (point 4) by using screws and washers of point 14, 16 and 17.



Place the concrete elements according to the illustration below:




• Connect upper surfaces of the concrete elements by using sheet metal connectors (point 7,8 and 9) and countersunk screws of point 15.





Screw the side rails (point 10, 11, 12, 13) to the concrete by using screws and washers of point 16 and 17.



- All the corners of the steel toe plates shall be mounted to the ground with the extension bolts of point 18
- Remove the slacks in joints
- Put the statutory plate